
Regional Portfolio Model Redevelopment Update

October 2014





Overview of Phase 1 Scope

- Phase 1 RPM Functionality
 - 1. 750 6th Plan Futures
 - 2. Calculate 20-year NPV
 - 3. Discretionary and Lost Opportunity Conservation
 - 4. CO2 emission tracking
 - 5. Dispatch of existing and new resources
 - 6. Economic RPS allocation
- Future functionality
 - 1. Optimization and efficient frontier
 - 2. Creation of futures



wcouncil.org

Redevelopment Progress

- Phase 1 Plan Calculation Logic
 - Delivered 1 week prior to contract deadline
 - Created distributions of model results from 750 input futures used to develop 6th Plan
 - Model outputs compared to results from RPM used in to develop 6th plan to test comparability
- Council staff and independent contractors (D. Logan and M. Schilmoeller) reviewed Phase 1 Model
- Systems Analysis Advisory Committee Scheduled to Preview Model
- Progress on Phase 2 ahead of schedule







Phase 1 - Preview


- Examples of model outputs
 - Optioned/Build Schedules
 - Conservation Development
 - Existing Plant Dispatch
 - Regional Imports/Exports
 - Cost to Serve Region
- Graphics from the model have a consistent look and feel, the following figures and graphs give a small preview of the redeveloped model.




nwcouncil.org











Is this a comparison of the existing and redeveloped dispatch of Boardman. If so, need to state that in title and show legend, because it isn't clear. If not, what is this telling us? Tom Eckman, 9/29/2014 TE3





Overview of phase 1 deliverable

Navigant compared output of the new RPM with output from the old RPM to the extent practicable.

- » Navigant compared output of the old RPM (model L813) with the new RPM for four distinct "plans," specifically:
 - Plan 2990 (Least Risk Plan)
 - Plan 4267 (Least Cost Plan)
 - Plan 3 (Minimalist Plan i.e., zero "optioned" resources)
 - Plan 4 (Maximal Plan i.e., many "optioned" resources)
- » Key outputs/performance indicators compared included:
 - NPV of 20-year cost to serve (including distribution of outcomes across all futures)
 - Equilibrium electricity prices over time (able to compare for two of the plans)
 - Capacity addition costs over time (an indicator of capacity addition algorithm similarity)
 - Model run times

©2012 Navigant Consulting, Inc.

11



Overview of phase 1 deliverable

Model differences will inevitably result in slightly different output.

- » Key model differences precluding exact output replication include -- in order of estimated importance (judgment based):
 - Equilibrium price algorithm
 - o New RPM has a more precise algorithm for finding equilibrium prices.
 - Algorithm finds the single, unique solution to congestion price (compared with old RPM, whose algorithm permits price differences without congestion)
 - Imperfections in reproduction of input data by Council staff
 - Price-responsive hydro (not in phase 1 RPM)
 - Demand response (not in phase 1 RPM)
 - Calculation of stochastic forced outages (not in phase 1 RPM)
 - Multi-phase construction (single phase in new RPM vs multi-phase in old RPM)

©2012 Navigant Consulting, Inc.

12



